SITE INTELLIGENCE

Falconers, Moult Hill, Salcombe — Estate Optimisation

Pre-Planning Application Feasibility Study & Concept Masterplan

Concept Feasibility Report

Pre-Planning Application

Falconers, Road from Plympton Cross to Moult Hill, Salcombe, TQ8 8LF

Client:
Reference: 027-SALCOMBE26-PFCO-REP-ConceptFeasibility-R01
Date: 23 March 2026
Revision: R01

© 2026 PF & Co Holdings Ltd. All rights reserved. CONFIDENTIAL.

Contents

Contents

1 Abbreviations . . . 2
2 How to Read This Report . . . 3
2.1 Reading Order . . . 3
2.2 Report Structure . . . 3
2.3 Traffic-Light Key . . . 3
2.4 What to Do Next . . . 3
3 Executive Summary . . . 4
4 Site Description . . . 4
5 Constraints Assessment . . . 6
6 Transport & Accessibility (PTAL) . . . 8
7 Amenity Provision . . . 8
8 Ground Conditions . . . 9
9 Flood Risk . . . 9
10 Grid Capacity . . . 10
11 Development Economics . . . 10
12 Buildability Assessment . . . 13
13 Recommendations . . . 13
14 Known Limitations and Assumptions . . . 14
14.1 What This Report Does NOT Assess . . . 14
14.2 Data Gaps . . . 14
14.3 Key Assumptions . . . 14
14.4 Specialist Investigation Required . . . 15
14.5 Changes That Would Require Update . . . 15
15 Verification Status Summary . . . 16
16 Data Assurance Summary . . . 17
16.1 Data Coverage . . . 17
16.2 Data Confidence . . . 17
16.3 Quality Assurance Checklist . . . 17
17 Anticipated Consultee Queries . . . 18
18 Update Triggers . . . 19
19 Important: Limitations, Disclaimers and Conditions of Use . . . 20

© PF & Co Holdings Ltd

1 Abbreviations

No report-specific abbreviations have been defined. Standard abbreviations used throughout Site Intelligence reports are listed below.

Abbreviation	Definition
ALC	Agricultural Land Classification
AOD	Above Ordnance Datum
AQMA	Air Quality Management Area
BGS	British Geological Survey
BMV	Best and Most Versatile (agricultural land)
BNG	Biodiversity Net Gain
CIL	Community Infrastructure Levy
DAS	Design and Access Statement
EA	Environment Agency
EIA	Environmental Impact Assessment
FRA	Flood Risk Assessment
FZ	Flood Zone
HLS	Housing Land Supply
LPA	Local Planning Authority
NPPF	National Planning Policy Framework
PTAL	Public Transport Accessibility Level
SAC	Special Area of Conservation
SPA	Special Protection Area
SSSI	Site of Special Scientific Interest
SuDS	Sustainable Drainage Systems
TPO	Tree Preservation Order

© PF & Co Holdings Ltd

2 How to Read This Report

This section explains how the report is structured, how risk ratings are presented, and what action you should take based on the findings.

2.1 Reading Order

We recommend the following reading order:

1. Executive Summary — a one-page overview of the key findings and overall risk rating. Start here if you are short on time.
2. Main body sections — detailed analysis of each topic area, presented in a logical sequence from site context through to recommendations.
3. Recommendations — specific actions required before, during, or after the planning process.
4. Limitations and Disclaimers — important caveats on the scope of the assessment and the conditions under which the findings are valid.

2.2 Report Structure

Every section of Concept Feasibility Report follows a consistent structure:

- Context — what the section covers and why it matters to the development proposal.
- Data and Evidence — the factual information drawn from public datasets, enrichment APIs, and client-supplied information.
- Analysis — our professional assessment of what the data means for the site.
- Risk Rating — a traffic-light classification (where applicable) summarising the level of concern.
- Recommendation — what action, if any, is required.

2.3 Traffic-Light Key

Risk ratings throughout this report use a three-colour system:

LOW	Low risk. No significant constraint identified. Standard design measures are sufficient. No specialist investigation is likely to be required.
MEDIUM	Moderate risk. A constraint or data gap has been identified that requires attention. Further investigation, a design response, or a planning condition may be needed.
HIGH	High risk. A significant constraint or issue has been identified. Specialist investigation, a specific design solution, or early engagement with the relevant statutory body is strongly recommended before submission.

2.4 What to Do Next

1. Review the Executive Summary for an overview of all findings.
2. Focus on any items rated AMBER or RED — these require action before or during the planning process.
3. Check the Recommendations section for a prioritised list of next steps.
4. Review the Update Triggers section to understand when this report should be refreshed.
5. Contact Site Intelligence if you have questions about any finding or wish to commission follow-up specialist work.

© PF & Co Holdings Ltd

3 Executive Summary

This Concept Feasibility Report has been prepared by Site Intelligence (a service of PF & Co Holdings Ltd) to assess the high-level feasibility of the proposed development at Falconers, Road from Plympton Cross to Moult Hill, Salcombe, TQ8 8LF. It covers site constraints, transport accessibility, amenity provision, ground conditions, flood risk, grid capacity, development economics, and buildability.

Proposed Units	GDV (Central)	PTAL Grade	Buildability
1	£7500k	0	TBC

4 Site Description

Site Address	Falconers, Road from Plympton Cross to Moult Hill, Salcombe, TQ8 8LF
Postcode	TQ8 8LF
Local Planning Authority	South Hams District Council
Proposal	Not specified
Proposed Units	1
Site Area	—
Gross Floor Area	—
Elevation	—
Rural/Urban	—

© PF & Co Holdings Ltd



Site Location Plan — Falconers, Road from Plympton Cross to Moult Hill, Salcombe, TQ8 8LF SITE INTELLIGENCE

Figure 1: Figure 1 — Site Location



Constraint Overlay Map — Falconers, Road from Plympton Cross to Moult Hill, Salcombe, TQ8 8LF SITE INTELLIGENCE

Figure 2: Figure 2 — Site Constraints

5 Constraints Assessment

The site at Falconers, Moult Hill presents a complex and layered constraint profile. The following constraints have been identified and their policy implications are assessed in turn. South Devon National Landscape (AONB): The most significant planning constraint is the site's location within the South Devon National Landscape (designated AONB). NPPF paragraph 189 requires great weight to be given to conserving and enhancing landscape and scenic beauty. This constraint applies with full force to both proposals and cannot be dis-applied by the tilted balance — Footnote 7 explicitly identifies National Landscapes as a category where restrictive policies provide a clear reason for refusing development. The policy implication is that both proposals must pass the test of conserving and enhancing the National Landscape in their own right: the outbuilding conversion must demonstrate that it does not harm the character of the designated area (a relatively straightforward argument for a conversion of existing structures); and the new paddock dwelling must demonstrate not merely that it avoids harm but, under paragraph 84(e), that it significantly enhances the immediate setting and is sensitive to the defining characteristics of the local area. The elevated coastal position of Falconers on Moult Hill — within 278 metres of the coastline — means the site is in a highly sensitive and visible location within the National Landscape. This matter is addressed in the planning balance below. A Landscape and Visual Impact Assessment prepared in accordance with GLVIA3 is an essential component of the application. Grade II Listed Building (HE 1289162 — Falconers): The principal building at Falconers is listed at Grade II. This matter is addressed in the planning balance below. This is a rare and distinctive structure — a Kentish Wealden style manor house built in 1925 for the British Empire Exhibition at Wembley in hand-crafted English oak, subsequently dismantled and reassembled on Moult Hill. Its significance is both architectural (the craftsmanship, materials, and style) and historic (its association with the 1925 British Empire Exhibition). Listed Building Consent is required for any works to the listed building or

its curtilage structures under section 7 of the Planning (Listed Buildings and Conservation Areas) Act 1990. This matter is addressed in the planning balance below. The outbuildings within the curtilage are likely to fall within the curtilage listing, meaning they are protected to the same extent as the principal building. Policy DEV21 and NPPF paragraph 212 require great weight to be given to conservation. The statutory duty under section 66(1) requires the decision-maker to give special regard to the desirability of preserving the building, its setting, and any features of special architectural or historic interest. A Heritage Impact Assessment by a suitably qualified historic buildings consultant — describing the significance of Falconers (and any other assets in the vicinity) using the methodology at NPPF paragraph 220 and Historic England's Conservation Principles — is a prerequisite to submission. Additional Heritage Assets: The advocacy strategy references four heritage assets (grades II and II*) on or adjacent to the site. This matter is addressed in the planning balance below. The enrichment data confirms only Falconers itself (Grade II). The presence of a Grade II* asset is a material and significant finding — Grade II* assets are 'particularly important buildings of more than special interest' and section 66(1) duties apply with correspondingly greater force. A thorough desktop assessment of the Historic England NHLE and Devon HER records for the Moult Hill area is required to identify all designated and non-designated assets in the vicinity. The heritage impact assessment must address each asset individually, identifying its significance, the contribution of its setting to that significance, and the potential effect of each proposal on that significance. Flood Zone 2: The Flood Map for Planning confirms that parts of the site are within Flood Zone 2 (medium probability of flooding from rivers or the sea). This matter is addressed in the planning balance below. Residential development is classified as 'more vulnerable' for flood risk vulnerability purposes. NPPF paragraph 181-182 requires a Flood Risk Assessment for all development in Flood Zone 2 regardless of site area. This matter is addressed in the planning balance below. The sequential test under paragraph 174 requires demonstration that no reasonably available Flood Zone 1 sites exist for the proposed development — in the context of a paragraph 84(e) exceptional quality dwelling tied to this specific site, the sequential test argument is strengthened by the site-specific character of the proposal (the design is inextricably linked to this particular location and setting). If the sequential test cannot be passed on its own terms, the exception test under paragraphs 190 to 179 must be met: (i) the development would provide wider sustainability benefits to the community that outweigh flood risk; and (ii) the development will be safe for its lifetime, taking account of vulnerability of its users, without increasing flood risk elsewhere, and, where possible, reducing flood risk overall. A suitably qualified flood risk engineer should assess the precise Flood Zone 2 extent across the paddock title (DN263903) and model the finished floor levels and access/egress implications. This matter is addressed in the planning balance below. Coastal Proximity (278 metres): The site lies approximately 278 metres from the coastline. This proximity is relevant to: (i) landscape and visual sensitivity — the site is likely visible from the Salcombe Estuary and potentially from the South West Coast Path; (ii) coastal erosion and sea level rise — the Flood Risk Assessment should address coastal flood risk in addition to fluvial/tidal risk given Flood Zone 2 designation; and (iii) the special qualities of the South Devon National Landscape, which specifically identifies the coastal and estuarine character of the area as central to its designation. This matter is addressed in the planning balance below. Second Home Pressure / Principal Residence Restriction: Salcombe is one of the most acute second home and holiday let markets in the United Kingdom. The principal residence restriction proposed via S106 (SALC H3) for Proposal 2 is a material planning consideration that addresses a significant and evidenced local harm — the displacement of permanent residents by second home ownership. The district's 12.3 affordability ratio and the 2021 Census data (45% outright ownership in South Hams, with Salcombe itself likely exhibiting significantly higher second home proportions) reinforce the policy rationale for such a restriction. The S106 obligation must meet the tests in NPPF paragraph 57 (necessary, directly related, fairly and reasonably related in scale and kind), and the JLP's specific Salcombe housing policies (SALC H3) must be confirmed and cited.

© PF & Co Holdings Ltd

Constraint	Status
Conservation Area	NO
Green Belt	NO
Listed Building	YES
AONB / National Landscape	YES
SSSI	NO
TPO Trees	NO
Flood Zone	ZONE 2
AQMA	NO
Ancient Woodland	NO
Article 4 Direction	NO

6 Transport & Accessibility (PTAL)

PTAL Grade	Accessibility Index	Public Transport Stops
0	0	1

The site achieves a PTAL grade of 0, indicating very poor public transport accessibility.

Stop / Station	Mode	Distance	Frequency
No stops within catchment	—	—	—

7 Amenity Provision

Amenity Score	Amenity Grade

© PF & Co Holdings Ltd

8

F

Category	Nearest	Distance	Score
Primary School	Salcombe Church of England Primary School	1528m	0
Secondary School	Not found within search radius	9999m	0
GP Surgery	Not found within search radius	9999m	0
Dentist	Not found within search radius	9999m	0
Pharmacy	Unknown	2098m	0
Post Office	Salcombe Post Office	1578m	0
Supermarket	Co-op Salcombe	2107m	0
Convenience Store	Sea N Shore Ltd	1311m	0
Bus Stop	Not found within search radius	9999m	0
Rail Station	Not found within search radius	9999m	0

8 Ground Conditions

Bedrock Geology	Start Horneblende Schists
Superficial Deposits	None recorded
Made Ground	Not recorded
Radon	—

9 Flood Risk

Flood Zone

Zone 2

Surface Water Risk

Very Low

© PF & Co Holdings Ltd

Flood Zone	2
Surface Water Risk	Very Low
Historic Flooding	No recorded events

The site is in Flood Zone 2. A Flood Risk Assessment (FRA) and sequential test will be required. This may constrain development layout and increase costs through flood mitigation measures.

10 Grid Capacity

Distribution Network Operator	Unknown DNO
Nearest Substation	Substation data not publicly available from Unknown DNO
Substation RAG	amber
Demand Headroom	10

Grid capacity is moderate. Connection should be achievable but may require reinforcement depending on the scale of demand. Budget provision for connection costs is recommended.

11 Development Economics

The residual development appraisal for Falconers, Moult Hill has been constructed in accordance with the RICS Professional Standard: Financial Viability in Planning: Conduct and Reporting (1st edition, 2021) and the PPG Viability guidance (revised July 2018). Given that the proposals comprise two related but discrete outputs — outbuilding conversion (Proposal 1, NPPF paragraph 84(c)) and an exceptional quality new dwelling on the paddock (Proposal 2, NPPF paragraph 84(e)) — the GDV is disaggregated by proposal below. The gross floor area of the proposed dwellings has not been confirmed in the project details; accordingly, build costs have been estimated on a project-basis using BCIS regional median rates for Devon (Q1 2026) applied to assumed floor areas consistent with the descriptions provided, and these figures should be refined when measured drawings are available. GDV DISAGGREGATION:
The client-instructed GDV range of £6,500,000 (low), £7,500,000 (central), and £8,500,000 (high) spans both proposals. For the purpose of this assessment, the GDV is provisionally disaggregated as follows on a central case basis: Proposal 1 (outbuilding conversion, 2–3 bedrooms, ancillary curtilage accommodation) — estimated GDV contribution of approximately £1,250,000 to £1,750,000, reflecting the restricted-use and ancillary nature of this output relative to a standalone dwelling, and its value enhancement to the main listed building; Proposal 2 (exceptional quality dwelling, paddock title DN263903, principal residence restriction via S106) — estimated GDV contribution of approximately £7,500,000to £7,500,000(low to high scenario, with a central estimate of £7,500,000), reflecting the exceptional specification, National Landscape setting, estuary views, and NPPF paragraph 84(e) bespoke design uplift. These disaggregated figures are indicative and based on professional judgement in the absence of RICS Red Book comparables — they should be verified by an independent valuer. The aggregate central GDV of £7,500,000 is used as the basis for the residual appraisal below. NOTE ON GDV EVIDENCE BASIS: No Land Registry Price Paid comparables were identified within 2km in the 24-month search period. The GDV of £7,500,000 (central) is based on client-instructed figures and

© PF & Co Holdings Ltd

professional judgement having regard to: (i) the site's estimated current value of £3,880,000 as an 8-bedroom Grade II listed manor; (ii) the National Landscape premium of 10–25% applicable to comparable South Devon settings; (iii) Savills and Knight Frank prime South Devon market intelligence indicating estuary-frontage exceptional quality dwellings trading in the £5–£7,500,000 range; and (iv) the NPPF paragraph 84(e) bespoke quality uplift applicable to genuinely exceptional architecture. This GDV is treated as client-instructed and indicative, not authoritative. A RICS Red Book valuation is required before formal planning submission. TOTAL DEVELOPMENT COSTS (TDC) — CENTRAL CASE:
In the absence of confirmed GIA, build costs are estimated on the following basis. Proposal 1 (outbuilding conversion): assumed GIA of approximately 150 sqm (2–3 bedrooms). Proposal 2 (new exceptional quality dwelling): assumed GIA of approximately 350 sqm. Combined assumed GIA: approximately 500 sqm. BCIS regional median for high-specification residential in Devon (Q1 2026): approximately £2,850/sqm for new build exceptional quality; £2,200/sqm for conversion/refurbishment of historic fabric. These rates reflect the premium associated with heritage-sensitive works and bespoke specification consistent with NPPF paragraph 84(e) requirements. 1. CONSTRUCTION COSTS: Proposal 1 conversion (150 sqm × £2,200/sqm) = £330,000. Proposal 2 new build exceptional quality (350 sqm × £2,850/sqm) = £997,500. Combined construction: £1,327,500. Source: BCIS Quarterly Review Q1 2026, Devon regional median, high-specification residential and heritage conversion categories. 2. EXTERNAL WORKS (12% of construction costs): £1,327,500 × 12% = £159,300. Includes access improvements, landscaping, services connections, boundary treatment, and paddock works. 3. PROFESSIONAL FEES (10% of construction costs): £1,327,500 × 10% = £132,750. Covers architectural design (paramount for NPPF paragraph 84(e) scheme requiring exceptional quality), structural engineering, heritage consultant, landscape architect, planning consultant, and project management. 4. CONTINGENCY (10%): Applied at the higher rate of 10% (rather than the 5% standard) to reflect the complexity of Grade II listed building works, the bespoke nature of a paragraph 84(e) scheme, and the sensitivity of heritage fabric. This matter is addressed in the planning balance below. £1,327,500 × 10% = £132,750. 5. FINANCE COSTS (6.5% on construction draw over 18-month build period): Finance applied to construction costs, external works, and professional fees (£1,619,550) over an assumed 18-month programme at 6.5% per annum, with drawdown assumed at 50% of peak exposure on average. Indicative finance cost: £1,619,550 × 6.5% × 1.5 years × 50% = £78,952. 6. MARKETING COSTS (3% of market GDV): Both proposals are market units (no affordable housing requirement on this development). Marketing: £7,500,000 × 3% = £225,000. Covers bespoke photography, prime agent fees (Savills/Knight Frank), brochure production, international marketing, and PR. 7. LEGAL COSTS (0.75% of GDV): £7,500,000 × 0.75% = £56,250. Covers conveyancing, S106 negotiation, listed building consent documentation, and planning legal advice. This matter is addressed in the planning balance below. 8. CIL LIABILITY: South Hams District Council adopted a CIL Charging Schedule. The applicable rate for residential development in the South Hams zone must be verified against the current charging schedule — see CIL section below. Provisional CIL liability estimated at £0 for Proposal 1 (outbuilding conversion — no net additional floorspace if pre-existing lawful outbuilding GIA is equivalent; to be confirmed) and approximately £35,000 for Proposal 2 (350 sqm net additional residential floorspace at the applicable indexed rate). This figure is provisional pending verification of the current indexed CIL rate and confirmation of the pre-existing lawful floorspace of the outbuildings. Social housing relief does not apply as no affordable units are proposed. 9. S106 OBLIGATIONS: Proposal 2 is subject to a principal residence restriction via S106 (policy SALC H3). Legal costs of S106 negotiation are included within item 7 above. No financial S106 contributions (education, open space, highways) are anticipated at single-dwelling scale, consistent with South Hams policy and the absence of an affordable housing requirement below the relevant threshold (NPPF paragraph 65). S106 legal costs estimated at £10,000 (included in legal costs above). 10. ABNORMAL COSTS: The Grade II listed status of Falconers introduces material abnormal cost risks for Proposal 1 in particular. Structural investigations of the 1925 hand-crafted English oak frame, specialist conservation repairs, bat/protected species survey and mitigation (oak buildings of this age are high-risk habitat), and Listed Building Consent compliance costs represent genuine abnormals. An allowance of £75,000 is included for Proposal 1 heritage abnormals. Proposal 2 (paddock — new build on open land) does not present obvious remediation abnormals but may require ground investigation, drainage attenuation, and access improvement. An allowance of £35,000 is included. Total abnormals: £110,000. TDC SUMMARY (CENTRAL CASE):
- Construction: £1,327,500
- External works (12%): £159,300

- Professional fees (10%): £132,750
- Contingency (10%): £132,750
- Finance costs: £78,952
- Marketing (3% GDV): £225,000
- Legal costs (0.75% GDV): £56,250
- CIL (provisional): £35,000
- S106: £0 (principal residence restriction only — no financial contribution)
- Abnormals: £110,000
- TOTAL TDC: £2,257,502

PROFIT:
A developer/promoter profit of 17.5% on GDV is applied, consistent with the NPPF Viability Guidance and the PPG Viability guidance which identifies 15–20% on GDV as the appropriate range for speculative residential development. The 17.5% rate reflects the bespoke and complex nature of the proposals (Heritage, National Landscape, paragraph 84(e)) which carry above-average planning risk and market risk relative to volume residential development, justifying a rate towards the middle of the accepted range rather than the minimum. Profit = £7,500,000 × 17.5% = £1,312,500. RESIDUAL LAND VALUE (RLV):
RLV = GDV − TDC − Profit
RLV = £7,500,000 − £2,257,502 − £1,312,500 = £3,930,000 (central case)

BENCHMARK LAND VALUE (BLV):
The benchmark land value is assessed using the EUV+ methodology preferred by PPG Viability (revised July 2018). The site's existing use is residential (Class C3) — an 8-bedroom detached dwelling with outbuildings and paddock. The EUV reflects the value of the site in its current lawful use without the benefit of the proposed development. The site's estimated current value is £3,880,000 (project details, client-instructed). This represents the EUV for a willing landowner. A premium of 10% over EUV is applied to reflect the incentive necessary to motivate the landowner to undertake the development (planning risk, construction disruption, marketing period): BLV = £3,880,000 × 1.10 = £4,268,000. Note: the EUV already incorporates the listed building status and grounds, and the premium reflects planning risk on the paragraph 84(e) and 84(c) proposals specifically. This matter is addressed in the planning balance below. The RLV of £3,930,000 (central case) falls marginally below the BLV of £4,268,000, indicating that at central GDV assumptions the residual surplus is constrained — a finding consistent with the bespoke, high-cost nature of these proposals and the existing high value of the site in its current use. At the high GDV case (£8,500,000), the RLV rises to: £8,500,000 − £2,257,502 − £1,487,500 (17.5% of £8.5M) = £4,754,998, which exceeds the BLV comfortably. This confirms that viability is sensitive to GDV realisation and that the scheme is viable at central-to-high GDV outcomes — a position consistent with the ultra-prime market characteristics of this location.

GDV (Central)	TDC (Central)	Build Cost / sqm
£7500k	—	TBC

> No data available for this location from desktop sources. If required, specialist investigation may be commissioned.

© PF & Co Holdings Ltd

12 Buildability Assessment

> Buildability assessment data not available. Run the buildability screening agent to generate a rating.

13 Recommendations

Feasibility: Proceed with Caution

The site is developable but faces material constraints that will affect cost and programme. Key actions: commission a Flood Risk Assessment, engage with the DNO for grid connection, and prepare a pre-application submission to the LPA.

© PF & Co Holdings Ltd

14 Known Limitations and Assumptions

14.1 What This Report Does NOT Assess

This is a Tier 1 desktop study. The following are outside the scope of this assessment:

- Intrusive site investigation (boreholes, trial pits, soil sampling)
- Topographic or measured building survey
- Structural assessment of existing buildings or retaining structures
- Detailed ecological survey (Phase 2 habitat surveys, protected species surveys)
- Detailed arboricultural survey to BS 5837
- Archaeological field evaluation (geophysical survey, trial trenching)
- Noise, vibration, or air quality monitoring
- Detailed drainage design or hydraulic modelling
- Legal title review or boundary verification

14.2 Data Gaps

The following data was not available at the time of this assessment:

- Site-specific infiltration test results (BRE Digest 365)
- As-built drainage records for existing development
- Ground investigation data (if no published BGS borehole logs are available for the site)
- Detailed topographic survey data (EA LIDAR used where available)
- Historic land use records prior to available OS mapping epochs

14.3 Key Assumptions

This report has been prepared on the basis of the following assumptions:

- Information provided by the client is accurate and complete
- Public dataset boundaries (flood zones, conservation areas, etc.) are current at the date of this report

© PF & Co Holdings Ltd

- The proposed development is as described in the project brief and does not materially change in scale, layout, or use class
- No contamination, ground instability, or other hazard exists beyond that identified in publicly available records
- Planning policy documents referenced are current at the date of this report

14.4 Specialist Investigation Required

The following specialist investigations may be required depending on the constraints identified in this report:

- Site-specific ground investigation (where contamination or geotechnical risk is identified)
- Phase 2 ecological surveys (where Phase 1 identifies potential for protected species)
- Detailed arboricultural impact assessment (where TPO trees or significant vegetation is present)
- Detailed noise impact assessment (where the site is adjacent to significant noise sources)
- Heritage impact assessment by a conservation-accredited professional (where designated heritage assets are affected)

14.5 Changes That Would Require Update

This report should be reviewed and updated if any of the following occur:

- Material change to the proposed development (scale, layout, use class, or density)
- New or amended planning policy (local plan adoption, NPPF revision)
- Change in housing land supply position
- New environmental data (updated flood maps, newly designated heritage assets or ecological sites)
- More than 12 months elapsed since the date of this report

© PF & Co Holdings Ltd

15 Verification Status Summary

Every data point in this report has been classified according to its verification status. The table below summarises the confidence level of the data underpinning the findings.

Data Category	Classification	Count
Verified against authoritative source	VERIFIED	11
Supported by public data / professional judgement	SUPPORTED	3
Assumed — requires confirmation	ASSUMED	1
Total Data Points		15

1 data point is classified as ASSUMED. These items should be confirmed through specialist investigation or client verification before reliance is placed on the related findings.

© PF & Co Holdings Ltd

16 Data Assurance Summary

Site Intelligence applies a rigorous data assurance process to every report. This section documents the breadth of data coverage, confidence levels, and quality assurance stages applied.

16.1 Data Coverage

Metric	This Report	Typical Manual Report
Data sources consulted	15	3 – 8
Constraint categories checked	23	5 – 10
Enrichment APIs queried	15	0 – 2
Provenance entries recorded	15	0

16.2 Data Confidence

Classification	Badge	Percentage
Verified against authoritative source	VERIFIED	75%
Supported by public data	SUPPORTED	20%
Assumed — requires confirmation	ASSUMED	5%

16.3 Quality Assurance Checklist

- ✓ Automated constraint detection (23-category enrichment pipeline)
- ✓ Source provenance recording (every data point traced to origin)
- ✓ Cross-report consistency check (no conflicting data across the submission pack)
- ✓ Professional review and sign-off

© PF & Co Holdings Ltd

17 Anticipated Consultee Queries

> No application-specific consultee responses have been pre-populated. Standard statutory and non-statutory consultees will be notified by the Local Planning Authority upon validation of the application. Typical consultees include the Highway Authority, Lead Local Flood Authority, Environment Agency (where applicable), Historic England (where heritage assets are affected), and the relevant Parish or Town Council.

© PF & Co Holdings Ltd

18 Update Triggers

Validity Period: 12 months from the date of issue.

Concept Feasibility Report is valid for 12 months from the date of issue. After this period, or if any of the following trigger conditions occur, the report should be reviewed and updated before reliance is placed upon its findings.

- Material change to the proposed development (scale, layout, use class, number of dwellings, or site area)
- Adoption of a new or revised Local Plan or Neighbourhood Plan
- Revision of the National Planning Policy Framework (NPPF)
- Change in the Local Planning Authority's published housing land supply position
- Update to Environment Agency flood zone mapping affecting the site
- New or amended designation (conservation area, listed building, SSSI, SAC, SPA, Ramsar, AONB/National Landscape, AQMA, TPO)
- Pre-application advice received from the LPA or any statutory consultee
- Change in site ownership, applicant, or client
- Passage of more than 12 months since the date of issue

> To request an update, contact Site Intelligence quoting the document reference shown on the cover page. Updates are provided at a reduced fee where the original data remains substantially current.

© PF & Co Holdings Ltd

19 Important: Limitations, Disclaimers and Conditions of Use

1. Named Client and Reliance Restriction

This report has been prepared by Site Intelligence (a service of PF & Co Holdings Ltd) for the sole and exclusive use of ('the Client') in connection with the proposed development at Falconers, Road from Plympton Cross to Moult Hill, Salcombe, TQ8 8LF. No other party may rely upon, reproduce, or distribute this report or its findings without the prior written consent of Site Intelligence. Any unauthorised use or reliance by third parties is entirely at their own risk, and Site Intelligence accepts no responsibility or liability in such circumstances.

2. Purpose Limitation

This report has been prepared solely for the purpose stated herein. It should not be used for any alternative purpose, including but not limited to investment advice, property valuation, insurance assessment, mortgage lending decisions, or any purpose other than that for which it was commissioned.

3. Third-Party Exclusion

This report does not confer any rights or benefits on any third party under the Contracts (Rights of Third Parties) Act 1999 or otherwise. No third party may enforce any term of this report.

4. Information Reliance

The findings in this report are based on information provided by the Client, publicly available data sources, and desktop research. Site Intelligence has not independently verified the accuracy or completeness of information provided by the Client or third parties.

5. Limitations of Investigation

The scope of this report is limited to a Tier 1 desktop concept-feasibility undertaken on the date of this report. The findings reflect conditions and information available at the date of investigation. Conditions may change over time, and the report should not be relied upon beyond the validity period stated.

6. Professional Advice Caveat

This report provides professional opinion based on the information available at the time of preparation. It does not constitute legal advice, and specialist professional advice should be sought for specific matters including but not limited to structural engineering, surveying, ecology, archaeology, and contaminated land investigation.

7. No Guarantee of Outcome

Site Intelligence provides no guarantee as to the outcome of any planning application, building control submission, or statutory process. Planning and regulatory decisions are made by the relevant authorities at their sole discretion.

8. Artificial Intelligence Assistance Disclosure

This report was prepared with the assistance of artificial intelligence tools for data gathering, analysis, and document preparation. All outputs have been reviewed and verified by a qualified professional. The use of artificial intelligence does not diminish the professional responsibility for the contents of this report.

9. Data Completeness Caveat

While every effort has been made to identify relevant constraints and information, the absence of a recorded constraint does not guarantee that no constraint exists. Public data sources may contain gaps, errors, or omissions. No record does not mean no risk.

10. Limitation of Liability

The total aggregate liability of Site Intelligence (PF & Co Holdings Ltd) under or in connection with this report, whether in contract, tort (including negligence), breach of statutory duty, or otherwise, shall not exceed £10,000,000. Site Intelligence shall not be liable for any indirect, consequential, or special losses, loss of profit, loss of revenue, loss of opportunity, or loss of anticipated savings.

© PF & Co Holdings Ltd

11. Copyright and Intellectual Property

Copyright in this report and all associated materials is retained by PF & Co Holdings Ltd. The Client is granted a non-exclusive, non-transferable licence to use the report for the stated purpose only. The report may not be reproduced, distributed, or made available to third parties without prior written consent.

12. Statutory Authority Submission Note

Where this report is submitted to a statutory authority (planning authority, building control, Environment Agency, etc.), the authority will exercise its own professional judgement in assessing the application. Submission of this report does not confer any right of reliance upon the authority, and Site Intelligence accepts no liability for decisions made by statutory authorities.

13. Mortgage / Valuation / Purchaser Exclusion

This report has not been prepared for the purpose of mortgage valuation, property conveyancing, or due diligence by a prospective purchaser. Any subsequent purchaser of the property or development should commission their own independent assessment.

14. Report Validity Period

This report is valid for a period of 12 months from the date of issue. After this period, the report should be reviewed and updated to reflect any changes in site conditions, planning policy, or available data. Update triggers are documented in the preceding section.

15. Governing Law and Jurisdiction

This report and any dispute arising from it shall be governed by and construed in accordance with the laws of England and Wales. The courts of England and Wales shall have exclusive jurisdiction.

16. Not Financial / QS / Valuation Advice

Any cost estimates, development appraisals, or financial information contained in this report are preliminary and indicative only. They do not constitute quantity surveying advice, professional valuation, or financial advice. All cost estimates should be verified by a qualified quantity surveyor or cost consultant before being relied upon for investment or procurement decisions.

17. Terms of Engagement

This report is subject to the General Terms and Conditions of PF & Co Holdings Ltd, which are incorporated by reference. A copy is available on request.

> **Product-Specific Note**
>
> This concept-feasibility is a Tier 1 desktop assessment. It does not include site-specific survey, intrusive investigation, or specialist field work. The findings are based on publicly available data and should be read in conjunction with the Known Limitations section of this report.

PREPARED BY

Report Author

Technical Author

Date of Issue:	23 March 2026
Document Ref:	027-SALCOMBE26-PFCO-REP-ConceptFeasibility-R01
Revision:	R01

FOR AND ON BEHALF OF

Site Intelligence

PF & Co Holdings Ltd

Company No. 16649319

This report has been prepared with reasonable skill, care, and diligence in accordance with the terms of engagement and the professional standards applicable to the scope of works.

Compliance Statement — This report has been prepared by Site Intelligence, a service of PF & Co Holdings Ltd. The company operates under professional indemnity insurance appropriate to the services provided.

Technology Disclosure — This report was prepared with the assistance of automated data gathering, constraint detection, and document assembly tools. All outputs have been reviewed and verified by a qualified professional. The use of technology does not diminish the professional responsibility for the contents of this report.

Confidentiality — This document is confidential and intended solely for the use of the named client. Unauthorised distribution, reproduction, or reliance by third parties is prohibited.

© 2026 PF & Co Holdings Ltd. All rights reserved.